

03	Vegetation clearance of site including uprooting of rank vegetation ,grass ,bush- wood, trees and sapling of girth upto 30 cm, measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared at equal interval and two times throughout the year as per the direction of site Incharge.	28,030.00 sqm																		
04	Provision for maintenance and servicing of diesel generator set and etc. throughout the year as per the direction of site Incharge																			
	(i)Diesel	350 litre																		
	(ii)Mobil	10 litre																		
	(iii)Repairing and servicing work As and when required	1 Unit(Whole item)																		

*This percentage, where no security deposit is taken will vary from 5 percent to 10 percent according to the requirement of the case. Where security deposit is taken see note to clause 1 of conditions of contract.